

Ref. No. 28.3.5/745/2026

Date: 17/07/2026

REQUEST FOR QUOTATIONS (RFQ)

PROPOSED WATERPROOFING WORK OF THE TOILETS OF ROOM NO 203, 204, 303, 304, 403, 404, 503, 504 AT THE GIRLS HOSTEL 'B' WING IN THE RESIDENTIAL CAMPUS OF GOKHALE INSTITUTE OF POLITICS & ECONOMICS, BMCC ROAD, SHIVAJINAGAR, PUNE-411004.

Gokhale Institute of Politics and Economics intends to undertake waterproofing work of the toilets of the room no 203, 204, 303, 304, 403, 404, 503, 504 of the Girls Hostel 'B' wing to protect the leakages to the adjacent rooms. The treatment may include various treatments including pressure grouting etc. The grouting materials & specifications are as bellow mentioned.

Sealed quotations/proposals are hereby invited from experienced agencies/contractors for carrying out the above mentioned civil works. The details of the work are specified in the attached Bill of Quantities (BOQ)/Work.


Interested agencies or their authorized representatives may visit the site to inspect the work and assess the scope of maintenance activities during the period 17th July 2026 to 21st July 2026, between 10:00 a.m. and 6:00 p.m.


Mr. Deepak Ganbawale (M: 9422043759) may be contacted for more details.

The quotations to be submitted on or before 21st July 2026 : 6.00 pm as per attached format.

Note:

- 1) BOQ / Format for Quotation is attached separately with the letter.
- 2) Quotations should be submitted as per attached format only & in one sealed envelope.





Kedar Tapikar
Administrative Officer

Toilet/Bathroom Injection Grouting & Tile Joint Filling

Annx	Description	Per Unit	Unit	Amount With Material
A)	Ladies Hostel Room Number 203,204		2	
B)	3rd Floor Ladies Hostel Room Number: 303, 304		2	
C)	4th Floor Ladies Hostel Room Number: 403, 404		2	
D)	5th Floor Ladies Hostel Room Number: 503, 504		2	
		Total	=	

Note:

- Chemicals to be used: Dr. Fixit or equivalent brand
- The quotations to be submitted in the format as above
- The scope of the work can be inspected by visiting the site.

Dr. Fixit Pidicrete URP:-

Cement: - 43 Grade Birla, ACC or equivalent

Epoxy: - Joint Filling Dr. Fixit product

Steps of the Waterproofing Work: -

1. Acid Wash
2. Tiles Joints cleaning
3. Drill 25MM Hole & Inject Chemical
4. Normal Wash
5. Rer Nani Trap with Crack Filling Powder U.R.P Chemical
6. Floor Masking
7. The Joints Feeling with Epoxy
8. Remove Masking Tape